



ใบแสดงปริมาณงาน

ELECTRICAL AND COMMUNICATION SYSTEM

SANITARY, PLUMBING AND FIRE PROTECTION SYSTEM

AIR CONDITIONING AND VENTILATION SYSTEM

PROJECT

XREPS

MAHANAKORN CUBE





PROJECT : XREPS
 LOCATION : MAHANAKORN CUBE
 SYSTEM :
 DATE : 28 APR2026
 CONTRACTOR : SANIT M&E CO., LTD.

ITEM	DESCRIPTION	UNIT	Q'TY	MATERIAL COST		LABOUR COST		TOTAL
				UNIT COST	TOTAL	UNIT COST	TOTAL	
1	METER PANEL BOARD AND MAIN DISTRIBUTION BOARD							
1.1	METER PANEL BOARD							
	- DIGITAL POWER METER	EA	2.00	6,000.00	12,000.00	1,500.00	3,000.00	15,000.00
	- CT'S 150/5A	EA	6.00	400.00	2,400.00	100.00	600.00	3,000.00
	- CONTROL FUSE	EA	2.00	500.00	1,000.00	100.00	200.00	1,200.00
	- PILOT LAMP	EA	6.00	150.00	900.00	50.00	300.00	1,200.00
	- CONTROL WIRING, CUBICLE AND BUSBARS	SET	2.00	6,000.00	12,000.00	5,000.00	10,000.00	22,000.00
	- ACCESSORIES	SET	2.00	8,000.00	16,000.00	3,000.00	6,000.00	22,000.00
1.2	MAIN DISTRIBUTION BOARD							
	- MCCB 3P-32AT I _c ≥18kA	EA	1.00	5,000.00	5,000.00	2,000.00	2,000.00	7,000.00
	- MCCB 3P-200AT I _c ≥18kA	EA	1.00	8,000.00	8,000.00	2,000.00	2,000.00	10,000.00
	TOTAL ITEM 1							81,400.00
2	PANEL BOARD AND CIRCUIT BREAKER							
2.1	PANEL BOARD							
	- LP 3Ph - 4W 12 ckt. Main CB 32A.	SET	1.00	9,000.00	9,000.00	1,000.00	1,000.00	10,000.00
	- LP 3Ph - 4W 42 ckt. Main CB 32A.	SET	1.00	27,000.00	27,000.00	1,000.00	1,000.00	28,000.00
2.2	MINIATURE CIRCUIT BREAKER							
	- RCBO 1P - 16AT IC ≥ 6KA	EA	2.00	1,800.00	3,600.00	120.00	240.00	3,840.00
	- RCBO 1P - 20AT IC ≥ 6KA	EA	1.00	1,800.00	1,800.00	120.00	120.00	1,920.00
	- RCBO 1P - 40AT IC ≥ 6KA	EA	7.00	1,800.00	12,600.00	120.00	840.00	13,440.00
	- 1P - 16AT IC ≥ 6KA	EA	16.00	150.00	2,400.00	120.00	1,920.00	4,320.00
	- 1P - 20AT IC ≥ 6KA	EA	5.00	150.00	750.00	120.00	600.00	1,350.00
	- 1P - 32AT IC ≥ 6KA	EA	1.00	150.00	150.00	120.00	120.00	270.00
	- 3P - 16AT IC ≥ 6KA	EA	4.00	2,500.00	10,000.00	300.00	1,200.00	11,200.00
2.3	CIRCUIT BREAKER							
	- ISOLATOR SW 3P - 20 AT	SET		1,000.00	-	500.00	-	-
	- ISOLATOR SW 3P - 32 AT	SET		1,000.00	-	500.00	-	-
	TOTAL ITEM 2							74,340.00



PROJECT : XREPS
 LOCATION : MAHANAKORN CUBE
 SYSTEM :
 DATE : 28 APR2026
 CONTRACTOR : SANIT M&E CO., LTD.

ITEM	DESCRIPTION	UNIT	Q'TY	MATERIAL COST		LABOUR COST		TOTAL
				UNIT COST	TOTAL	UNIT COST	TOTAL	
3	CABLE AND CONDUIT & RACE WAY							
3.1	CABLE							
	IEC01							
	- IEC01 - 1.5 mm. ²	M		12.00	-	10.00	-	-
	- IEC01 - 2.5 mm. ²	M	1,900.00	18.00	34,200.00	10.00	19,000.00	53,200.00
	- IEC01 - 4 mm. ²	M	1,700.00	28.00	47,600.00	10.00	17,000.00	64,600.00
	- IEC01 - 6 mm. ²	M	60.00	40.00	2,400.00	10.00	600.00	3,000.00
	- IEC01 - 10 mm. ²	M	1,000.00	65.00	65,000.00	10.00	10,000.00	75,000.00
	- IEC01 - 16 mm. ²	M	40.00	110.00	4,400.00	40.00	1,600.00	6,000.00
	- IEC01 - 120 mm. ²	M	160.00	780.00	124,800.00	200.00	32,000.00	156,800.00
	- CV - 2.5 mm. ²	M	300.00	40.00	12,000.00	10.00	3,000.00	15,000.00
	- FRC - 2.5 mm. ²	M	120.00	70.00	8,400.00	15.00	1,800.00	10,200.00
	SUB TOTAL ITEM 3.1							
3.2	CONDUIT & RACE WAY							
	- WIRE WAY 100 x 100 mm. (ความหนา = 1.2 mm.)	M			-		-	-
	- WIRE WAY 150 x 100 mm. (ความหนา = 1.2 mm.)	M			-		-	-
	- Dia 1/2" EMT	M	600.00	30.00	18,000.00	20.00	12,000.00	30,000.00
	- Dia 3/4" EMT	M	80.00	40.00	3,200.00	20.00	1,600.00	4,800.00
	- Dia 1" EMT	M	400.00	75.00	30,000.00	30.00	12,000.00	42,000.00
	- Dia 1/2" IMC	M			-		-	-
	- Dia 1" IMC	M	30.00	130.00	3,900.00	60.00	1,800.00	5,700.00
	- Dia 2-1/2" IMC	M	30.00	460.00	13,800.00	200.00	6,000.00	19,800.00
	- LIQUIDTIGHT FLEXIBLE METAL CONDUIT (LFMC)	LOT			-		-	-
	- FLEXIBLE CONDUIT	LOT	1.00	8,000.00	8,000.00	3,000.00	3,000.00	11,000.00
	- FITTING AND SUPPORT	LOT	1.00	8,000.00	8,000.00	3,000.00	3,000.00	11,000.00
	- ACCESSORIES	LOT	1.00	8,000.00	8,000.00	3,000.00	3,000.00	11,000.00
	SUB TOTAL ITEM 3.2							
	TOTAL ITEM 3							519,100.00



PROJECT : XREPS
 LOCATION : MAHANAKORN CUBE
 SYSTEM :
 DATE : 28 APR2026
 CONTRACTOR : SANIT M&E CO., LTD.

ITEM	DESCRIPTION	UNIT	Q'TY	MATERIAL COST		LABOUR COST		TOTAL
				UNIT COST	TOTAL	UNIT COST	TOTAL	
4	LIGHTING FIXTURE							
	- TYPE "EM1" ADJUSTABLE LED RECESSED DOWNLIGHT							
	FOR EMERGENCY LIGHT REMOTE LAMP	SET	10.00	800.00	8,000.00	300.00	3,000.00	11,000.00
	- TYPE " D1" 6W ADJUSTABLE RECESSED DOWNLIGHT	SET	9.00	EXCLUDE		300.00	2,700.00	2,700.00
	- TYPE " D3" 4.9W ADJUSTABLE RECESSED DOWNLIGHT	SET	24.00	EXCLUDE		300.00	7,200.00	7,200.00
	- TYPE " D4" 4.9W ADJUSTABLE RECESSED DOWNLIGHT	SET	7.00	EXCLUDE		300.00	2,100.00	2,100.00
	- TYPE " D5" 3W MINI RECESSED DOWNLIGHT	SET	16.00	EXCLUDE		300.00	4,800.00	4,800.00
	- TYPE " D6" 10W SURFACE MOUNTED LINEAR LIGHT	SET	2.00	EXCLUDE		300.00	600.00	600.00
	- TYPE " S1" 5W MAGNETIC TRACK LIGHT	SET	15.00	EXCLUDE		300.00	4,500.00	4,500.00
	- TYPE " S2" 5W LED OUTDOOR SPOT LIGHT	SET	5.00	EXCLUDE		300.00	1,500.00	1,500.00
	- TYPE " L1" RGBW LED STRIP LIGHT	M	235.00	EXCLUDE		120.00	28,200.00	28,200.00
	- TYPE " L2" LED STRIP LIGHT	M	3.00	EXCLUDE		120.00	360.00	360.00
	- TYPE " L3" LED STRIP LIGHT	M	11.00	EXCLUDE		120.00	1,320.00	1,320.00
	- TYPE " L4" LED NEON FLEX 9.6W/m.	M	67.00	EXCLUDE		120.00	8,040.00	8,040.00
	- 9W. LED TUBE, DAYLIGHT 6500K, BARE TYPE	SET	4.00	350.00	1,400.00	300.00	1,200.00	2,600.00
	- EMERGENCY EXIT SIGN	SET	2.00	3,000.00	6,000.00	300.00	600.00	6,600.00
	- EMERGENCY LIGHT CENTRAL UNIT 50 W. 12V	EA	1.00	4,000.00	4,000.00	1,000.00	1,000.00	5,000.00
	TOTAL ITEM 4							86,520.00
5	SWITCH AND POWER OUTLET							
	- 1-WAY SWITCH 16A. 250Vac. (1Ch.)	EA	15.00	80.00	1,200.00	80.00	1,200.00	2,400.00
	- 1-GANG PLASTIC PLATE	EA	3.00	30.00	90.00		-	90.00
	- 2-GANG PLASTIC PLATE	EA	6.00	30.00	180.00		-	180.00
	- 3-GANG PLASTIC PLATE	EA	22.00	30.00	660.00		-	660.00
	- WEATHER PROOF COVER	EA	1.00	150.00	150.00	80.00	80.00	230.00
	- GROUNDING SIMPLEX RECEPTACLE 16 A. 250Vac.	EA		150.00	-	120.00	-	-
	- GROUNDING DUPLEX RECEPTACLE 16 A. 250Vac.	EA	22.00	200.00	4,400.00	120.00	2,640.00	7,040.00
	- JUNCTION FOR SWITCH & OUTLET & ELEC. EQUIPMENT	EA	42.00	30.00	1,260.00		-	1,260.00
	- ACCESSORIES	LOT	1.00	8,000.00	8,000.00	3,500.00	3,500.00	11,500.00
	TOTAL ITEM 5							23,360.00



PROJECT : XREPS
 LOCATION : MAHANAKORN CUBE
 SYSTEM :
 DATE : 28 APR2026
 CONTRACTOR : SANIT M&E CO., LTD.

ITEM	DESCRIPTION	UNIT	Q'TY	MATERIAL COST		LABOUR COST		TOTAL
				UNIT COST	TOTAL	UNIT COST	TOTAL	
6	COMPUTER NETWORK SYSTEM							
	- DATA RACK 6U w/VENTILATION FAN	SET	1.00	4,500.00	4,500.00	1,500.00	1,500.00	6,000.00
	- GIGABIT SWITCHING HUB 16 PORT	SET	1.00	3,500.00	3,500.00	1,000.00	1,000.00	4,500.00
	- CAT6 DATA MODULAR JACK (1Ch.)	EA	6.00	300.00	1,800.00	120.00	720.00	2,520.00
	- 1-GANG PLASTIC PLATE	EA	6.00	30.00	180.00		-	180.00
	- 2-GANG PLASTIC PLATE	EA		30.00	-		-	-
	- BOX FOR SWITCH & OUTLET	EA	6.00	30.00	180.00		-	180.00
	- UTP CAT6 CABLE	M	140.00	18.00	2,520.00	10.00	1,400.00	3,920.00
	- WIRE WAY 100 x 50 mm. (ความหนา = 1.2 mm.)	M			-		-	-
	- Dia 1/2" EMT	M	100.00	30.00	3,000.00	20.00	2,000.00	5,000.00
	- Dia 3/4" EMT	M	40.00	40.00	1,600.00	20.00	800.00	2,400.00
	- FITTING AND SUPPORT	LOT	1.00	3,000.00	3,000.00	1,000.00	1,000.00	4,000.00
	- ACCESSORIES	LOT	1.00	3,000.00	3,000.00	1,000.00	1,000.00	4,000.00
	TOTAL ITEM 6							32,700.00
7	FIRE ALARM SYSTEM							
	- SMOKE DETECTOR	EA	13.00	1,500.00	19,500.00	500.00	6,500.00	6,500.00
	- HEAT DETECTOR FIXED TEMPERATURE TYPE 194°F & RATE OF RISE 15°F/MIN (NEW)	EA			-		-	-
	- IEC01 - 1.5 mm. ²	M	500.00	12.00	6,000.00	10.00	5,000.00	5,000.00
	- Dia 1/2" EMT	M	480.00	30.00	14,400.00	20.00	9,600.00	24,000.00
	- FLEXIBLE CONDUIT	M	20.00	10.00	200.00	10.00	200.00	400.00
	- FITTING AND SUPPORT	LOT	1.00	3,000.00	3,000.00	1,000.00	1,000.00	4,000.00
	- ACCESSORIES	LOT	1.00	3,000.00	3,000.00	1,000.00	1,000.00	4,000.00
	TOTAL ITEM 7							43,900.00



PROJECT : XREPS
 LOCATION : MAHANAKORN CUBE
 SYSTEM :
 DATE : 28 APR2026
 CONTRACTOR : SANIT M&E CO., LTD.

ITEM	DESCRIPTION	UNIT	Q'TY	MATERIAL COST		LABOUR COST		TOTAL
				UNIT COST	TOTAL	UNIT COST	TOTAL	
8	SOUND SYSTEM - BY OTHER ส่งไม่ทัน							
	- POWER AMP 60W.	EA			-		-	-
	- MEDIA PLAYER	EA			-		-	-
	- LOUD SPEAKER WALL TYPE 6W.	EA			-		-	-
	- 2C x 2.5 mm. ² - VTF	M			-		-	-
	- Dia 1/2" EMT	M			-		-	-
	- Dia 1/2" IMC	M			-		-	-
	- FITTING AND SUPPORT	LOT			-		-	-
	- ACCESSORIES	LOT			-		-	-
	TOTAL ITEM 8							-
9	CCTV SYSTEM							
	- NETWORK VIDEO RECORDER, NVR	SET	1.00	16,000.00	16,000.00	2,000.00	2,000.00	18,000.00
	- COLOUR IP CCTV CAMERA 1/3" CMOS H.265+, DOME TYPE	EA	7.00	2,000.00	14,000.00	300.00	2,100.00	16,100.00
	- COLOUR IP CCTV CAMERA 1/3" CMOS H.265+, SURFACE MOUNTE	EA			-		-	-
	- UTP CAT6 CABLE	M	140.00	18.00	2,520.00	10.00	1,400.00	3,920.00
	- Dia 1/2" EMT	M	140.00	30.00	4,200.00	20.00	2,800.00	7,000.00
	- FITTING AND SUPPORT	LOT	1.00	3,000.00	3,000.00	1,000.00	1,000.00	4,000.00
	- ACCESSORIES	LOT	1.00	3,000.00	3,000.00	1,000.00	1,000.00	4,000.00
	TOTAL ITEM 9							53,020.00
	TOTAL 1 - 9							914,340.00



PROJECT : XREPS
LOCATION : MAHANAKORN CUBE
SYSTEM
DATE : 28 APR2026
CONTRACTOR : SANIT M&E CO., LTD.

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL COST		LABOUR COST		TOTAL
				UNIT COST	TOTAL	UNIT COST	TOTAL	
1	COLD AND HOT WATER SYSTEM							
1.1	COLD WATER PIPE (PPR; PN10)							
	- Dia. 1"	M			-		-	-
	- FITTING	LOT			-		-	-
	- HANGER & SUPPORT	LOT			-		-	-
1.2	HOT WATER PIPE (PPR; PN20)							
	- Dia. 1/2"	M			-		-	-
	- Dia. 3/4"	M			-		-	-
	- Dia. 1"	M			-		-	-
	- FITTING	LOT			-		-	-
	- HANGER & SUPPORT	LOT			-		-	-
1.3	BALL VALVE							
	- Dia. 1/2"	PCS			-		-	-
	- Dia. 1"	PCS			-		-	-
1.4	HOSE BIBB							
	- Dia. 1/2"	PCS			-		-	-
1.5	MAIN WATER FILTER(10")	SET			-		-	-
1.6	DRINKING WATER FITER	SET			-		-	-
1.7	WATER METER							
	- Dia. 1" (Existing)	PCS			Not Include		-	-
	TOTAL ITEM 1							-
2	WASTE SYSTEM							



PROJECT : XREPS
LOCATION : MAHANAKORN CUBE
SYSTEM
DATE : 28 APR2026
CONTRACTOR : SANIT M&E CO., LTD.

ITEM	DESCRIPTION	UNIT	Q'TY	MATERIAL COST		LABOUR COST		TOTAL
				UNIT COST	TOTAL	UNIT COST	TOTAL	
2.1	WASTE PIPE ,D, (PVC CLASS 13.5)							
	- Dia. 2"	M						
	- Dia. 3"	M						
	- FITTING & SUPPORT	LOT						
2.2	WASTE PIPE, D (SS 304(SML)ASTM A312)							
	- Dia. 2"	M						
	- Dia. 2-1/2"	M						
	- FITTING & SUPPORT	LOT						
2.3	INSULATION PIPE (THICK-1/2")							
	- CLOSE CELL ELASTOMERIC FOAM	M						
2.4	FLOOR CLEANOUT							
	- Dia. 2"	PCS						
2.5	FLOOR CLEANOUT							
	- Dia. 4"	PCS						
	TOTAL ITEM 2							
3	FIRE PROTECTION SYSTEM							
3.1	SP PIPE (BSP SEAM SCHEDULE 40)	LOT	1.00	30,000.00	30,000.00	45,000.00	45,000.00	75,000.00
	- FITTING	LOT	1.00	15,000.00	15,000.00		-	15,000.00
	- HANGER & SUPPORT	LOT	1.00	15,000.00	15,000.00		-	15,000.00
3.2	NEW WALL TYPE SPRINKLER HEAD	PCS	3.00	400.00	1,200.00		-	1,200.00
3.3	NEW PENDENT SPRINKLER HEAD (68°C)	PCS	18.00	400.00	7,200.00		-	7,200.00
3.4	NEW UPRIGHT SPRINKLER HEAD	PCS	8.00	400.00	3,200.00		-	3,200.00
	TOTAL ITEM 3							116,600.00
	TOTAL 1 – 3							116,600.00



PROJECT : XREPS
 LOCATION : MAHANAKORN CUBE
 SYSTEM :
 DATE : 28 APR2026
 CONTRACTOR : SANIT M&E CO., LTD.

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL COST		LABOUR COST		TOTAL
				UNIT COST	TOTAL	UNIT COST	TOTAL	
A	AIR CONDITIONER AND VENTILLATION SYSTEM							
1.1	AIR HANDLING UNIT CHILLED WATER							
	- AHU-01 (120,000 BTUH) (DUCT TYPE) - RELOCATE	SET	1.00		-	30,000.00	30,000.00	30,000.00
	- AHU-02 (120,000 BTUH) (DUCT TYPE) - RELOCATE	SET	1.00		-	30,000.00	30,000.00	30,000.00
	- AHU-03 (120,000 BTUH) (DUCT TYPE) - EXISTING	SET	1.00		-		-	-
	- AHU-04 (100,000 BTUH) (DUCT TYPE) - NEW	SET	1.00	120,000.00	120,000.00	20,000.00	20,000.00	140,000.00
	- FCU-01 (18,000 BTUH) - NEW	SET	1.00	30,000.00	30,000.00	10,000.00	10,000.00	40,000.00
1.2	VENTILLATION SYSTEM							
	- EF-1 CEILING MOUNTED / DIRECT DRIVE FAN	SET	1.00	12,000.00	12,000.00	2,000.00	2,000.00	14,000.00
	- EF-2 CEILING MOUNTED / DIRECT DRIVE FAN	SET	1.00	12,000.00	12,000.00	2,000.00	2,000.00	14,000.00
	- EF-3 CEILING MOUNTED / DIRECT DRIVE FAN	SET	1.00	12,000.00	12,000.00	2,000.00	2,000.00	14,000.00
	- AIR CURTAIN	SET	2.00	15,000.00	30,000.00	2,000.00	4,000.00	34,000.00
	AIR CHAMBER							
	Gypsum board thk. 9 mm.	SET	4.00	8,000.00	32,000.00	3,000.00	12,000.00	44,000.00
	Service catwalk	SET	3.00	5,000.00	15,000.00	2,000.00	6,000.00	21,000.00
	SUPPORT & HANGER	LOT	1.00	20,000.00	20,000.00	5,000.00	5,000.00	25,000.00
	FITTING & ACCESSORIES	LOT	1.00	10,000.00	10,000.00	2,000.00	2,000.00	12,000.00
1.3	PIPING WORK							
	Black Steel SCH 40 seam							
	- Dia 2-1/2"	M	9.00	500.00	4,500.00	350.00	3,150.00	7,650.00
	- Dia 1-1/2"	M	30.00	400.00	12,000.00	250.00	7,500.00	19,500.00
	- Dia 3/4"	M	20.00	250.00	5,000.00	150.00	3,000.00	8,000.00
	SUPPORT & HANGER	LOT	1.00	10,000.00	10,000.00		-	10,000.00
	FITTING & ACCESSORIES	LOT	1.00	6,000.00	6,000.00		-	6,000.00
	Close Cell Insulation For CHS/CHR Pipe (1" THK)							
	- Dia 2-1/2"	M	9.00	500.00	4,500.00	300.00	2,700.00	7,200.00
	- Dia 2-1/2"	M	30.00	350.00	10,500.00	200.00	6,000.00	16,500.00
	- Dia 3/4"	M	20.00	200.00	4,000.00	100.00	2,000.00	6,000.00
	- Adhesive and tape	LOT	1.00	2,000.00	2,000.00		-	2,000.00
	Condensate Drain Pipe (PVC Class 8.5)							
	- Dia 1 1/4"	M	10.00	120.00	1,200.00	120.00	1,200.00	2,400.00
	SUPPORT & HANGER	LOT	1.00	1,000.00	1,000.00		-	1,000.00
	FITTING & ACCESSORIES	LOT	1.00	500.00	500.00		-	500.00



PROJECT : XREPS
LOCATION : MAHANAKORN CUBE
SYSTEM :
DATE : 28 APR2026
CONTRACTOR : SANIT M&E CO., LTD.

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL COST		LABOUR COST		TOTAL
				UNIT COST	TOTAL	UNIT COST	TOTAL	
	Close Cell Insulation For Condensate Drain Pipe (1/2" THK)							
	- Dia 1 1/4"	M	10.00	200.00	2,000.00	100.00	1,000.00	3,000.00
	ADHESIVE	LOT	1.00	1,000.00	1,000.00		-	1,000.00
1.4	2-WAY PICV VALVE	SET	2.00	37,000.00	74,000.00	3,000.00	6,000.00	80,000.00
1.5	LCD ROOM TEMP. CONTROLLER	SET	2.00	8,500.00	17,000.00	1,000.00	2,000.00	19,000.00
1.6	DUCT WORK							
	งานรีดลอนท่อลมเก่า	LOT	1.00			15,000.00	15,000.00	15,000.00
	GALVANIZED STEEL SHEET							
	- # 26	Sq.ft.	1,830.00	40.00	73,200.00	30.00	54,900.00	128,100.00
	- # 24	Sq.ft.	2,600.00	50.00	130,000.00	30.00	78,000.00	208,000.00
	SUPPORT & HANGER	LOT	1.00	16,000.00	16,000.00	8,500.00	8,500.00	24,500.00
	FITTING & ACCESSORIES	LOT	1.00	5,000.00	5,000.00	3,000.00	3,000.00	8,000.00
	INSULATION FIBER GLASS 1" THK,2lb/ft	Sq.ft.	4,430.00	20.00	88,600.00	15.00	66,450.00	155,050.00
	ADHESIVE AND TAPE	LOT	1.00	15,000.00	15,000.00		-	15,000.00
	SUPPLY AIR SQUARE CEILING DIFFUSER							
	- SIZE 16"x16" W/VD	SET	11.00	3,000.00	33,000.00	1,000.00	11,000.00	44,000.00
	- SIZE 12"x12" W/VD	SET	1.00	2,000.00	2,000.00	1,000.00	1,000.00	3,000.00
	- SIZE 10"x10" W/VD	SET	4.00	1,500.00	6,000.00	500.00	2,000.00	8,000.00
	LINEAR SLOT SUPPLY AIR DIFFUSER							
	- 3LSD 3/4" X LENGTH 3.0 M. W/VD	SET	8.00	5,000.00	40,000.00	1,500.00	12,000.00	52,000.00
	RETURN AIR GRILLE							
	- SIZE 24"x48" W/BLACK NYLON FILTER	SET	2.00	4,500.00	9,000.00	1,500.00	3,000.00	12,000.00

